

## CURRENT SITE



# PROPOSED AND APPROVED CHANGE





SHEET: 1 OF 1  
 JOB NAME: SCC-Firing Range  
 JOB NO: \_\_\_\_\_ DATE: 8/15/19  
 TITLE: \_\_\_\_\_ Bid Form

Prepared By: Tony Hauser, PLA, PE  
 Checked By: Matthew E. Wallace, PE

**Bid Form**

Item Description	Unit	Estimated Quantity	Bidder Quantity	Unit Cost	Total Cost
Mobilization	LS	1			
Surveying & Utility Locate	LS	1			
<b>Demolition</b>					
Clearing & Grubbing	SY	2079			
Strip & Stockpile Topsoil - 6" Depth	CY	346			
Remove Flag Pole	LS	1			
Remove Light Pole	LS	1			
Remove RR-Tie Wall	LS	1			
Remove Masonry Block Wall	LS	1			
Remove Skeet House	LS	1			
Remove Target System Controls Wall	LS	1			
<b>Erosion Control (3 Phases)</b>					
Construction Entrance	EA	1			
Compost Filter Sock	LF	675			
Silt Fence	LF	230			
Silt Fence Outlet	EA	1			
Block and Gravel Inlet Protection	EA	1			
Rock Pipe Inlet Protection	EA	1			
French Drain Ring	LF	250			
4" HDPE Drain - Solid & Perf'd.	LF	200			
Rip Rap Outlet Protection	EA	1			
Replace Topsoil	CY	346			
<b>Site Improvements</b>					
Excavate & Stockpile Soil	CY	2500			
Backfill & Compact Soil	CY	2500			
Install Diversion Ditches above Backstop	LF	375			
Eco-Block Wall at Target	FF	72			
Ballistic Rubber on Wall	SF	20			
8' Eco-Block Lane Wall	FF	1652			
4' Eco-Block Wall	FF	720			
Masonry Block Wall w/ Wood Facing	FF	54			
HDPE Wrapped Lead Materials	LS	1			
Install 2" Conduits	LF	310			
Install Backstop/Target					
Ballistic Sand	CY	141			
Geomembrane	SF	4033			
Shotcrete	SF	1900			
Poly Liner	SF	2200			
Slope Drain Aggregate	CY	278			
Install Sump					
12" Dia. Pipe	LF	90			
Geotextile Fabric	SF	900			
Washed Stone	CY	25			

Install Modified 40'x8' Conex Box	LS	1			
Reinstall Light	LS	1			
Extend Electrical to Conex	LS	1			
Construct 2 Shooting Lanes	LS	1			
Concrete Flatwork	SF	1130			
Gravel Surface	CY	18			
Aggregate Base	CY	24			
4' Block Wall	FF	72			
Reinstall Flag Pole	LS	1			
6" Compacted ABC Parking Area	CY	25			
<b>Landscape Improvements</b>					
Eastern Red Cedar	EA	18			
Nellie Stevens Holly	EA	18			
Leyland Cypress	EA	28			
Permanent Seeding	SY	2079			
<b>Miscellaneous</b>					
Trench Rock Removal	CY	0			
Mass Rock Removal	CY	0			
<b>Total Bid</b>					
<b>Unit</b>					
Abbreviation	Meaning				
EA	Each				
FF	Face Feet				
SY	Square Yard				
SF	Square Foot				
LF	Linear Foot				
LS	Lump Sum				
AC	Acre				
CY	Cubic Yard				
TN	Ton				
		<p><b>Note:</b></p> <ol style="list-style-type: none"> <li>1. All quantities shall be verified by the Bidder in the column provided.</li> <li>2. All unit costs shall be provided irrespective of a zero quantity.</li> <li>3. Allowances shall be provided at the quantities shown.</li> <li>4. It is the intent of the Contract Documents to describe a functionally complete project. Any labor, documentation, services, materials, or equipment that reasonably may be inferred from the Contract Documents or from prevailing custom or trade usage as being required to produce the indicated result will be provided whether or not specifically called for, at no additional cost to the Owner.</li> <li>5. Items required by the plans but not listed above shall be brought to the attention of the engineer.</li> </ol>			